



www.modalart.com info@modalart.com Ph 203 570 0150 Fx 888 908 7071

Date: 26/01/2017

Module MArt01 - 20'

Change Rate = 1\$ = 0.9233€

FOB Italy

Code	Description	Unit	Quantity	Price		Total Price
				USA Price	Price	
				\$	€	\$
T001	modalART roof (A= 12 mt beams)* See the attached sketch for the calculation of the square meters (A x B) Inflatable beams anodized alu profiles, silver color, alloy 6005 Zinc coated side plates for the fixing on the roof (see the attached sketch) polyuretane beams Inner membrane polyurethane/nylon fiber beams outer membrane pvc or polyuretane/nylon fiber connecting canvasses between the inflatable beams (waterproof and fire resistant); color white Pneumatic equipment: electric blower, tubes, safety valves	sqmt	72	\$ 487.38	€ 450.00	\$ 35,091.52
T013	Pre-assembly of support steel plates, air control unit, wiring, inflatable tubes system, electrical*	n.	1	\$ 1,624.61	€ 1,500.00	\$ 1,624.61
	tot.					\$ 36,716.13
T014	First Installation Supervision*(if requested)	day	3	\$ 649.84	€ 600.00	\$ 1,949.53

Lead time approx. 6 weeks after design approval

Prices valid up to 31st December 2017