




www.modalart.com info@modalart.com Ph 203 570 0150 Fx 888 908 7071


**\*NOTES**

T001	The Roof has been designed to be fixed directly on the Container Roof through Steel Plates. The level of the Inflated beams depends on the positioning of the container directly on the ground or on spacers.
T002	The vertical plexiglas transparent panels for cladding will be supplied in 1.0 x 1.0m modules, with an aluminium frame, to be fixed on vertical and horizontal alu posts. It is possible to have different size panels up to 3.0 x 2.0m, to be quoted.
T009	The logo or coloring of the beams has been considered only for the front and back beams and for the half visible beam surface (around 9sqmt/each beam)
T010	The offered decking is an easy to install and high durability flooring system used for exterior uses (see attached documentation), high quality.
T011	<p>The air conditioning system has been calculated for the volume underneath the Tensairity roof, not for the additional containers volumes. In case needed also for that volumes we can design a new system. The system has dimensioned for an external working temperature Of 30-32°C, and a temperature abatment of around 11°C with a <b>30 volumes/hour</b> air circulation.</p> <p>The machines have been designed to stay inside the containers, modifying one side of a container to let it be sliding and to be open during working. The container modification is not included. Attached the type of machines included.</p> <p>The duct system has been designed to be in microperforated PVC material, to be fixed under the inflated beams, with a diameter of 400-500mm.</p> <p>The ducts will be attached to an easy flange system to be prepared on the interior side of the containers</p>
T014	Excluded Flights, Hotels and meals to be approved and payed in advance

General	<p>The prices are all Ex Works</p> <p><b>Estimated</b> CIF price for New York and Rio are*</p> <p><b>Italy / cy New York (included CYC costs)</b></p> <p>40' Container - maximum 21tonn = € 3.350.00 =</p> <p>20' Container - maximum 18tonn = € 2.850.00 =</p> <p>all risk insurance = 0.35% on Invoicing amount excluded</p> <p>*All the transport, taxes and duties will be calculated on the effective items orderd and updated in the precise period of the delivery</p> <p>Delivery Costs Estimation (to be considered as guide-lines)</p> <p><b>NEW YORK:</b></p> <p>Not included: Marine insurance, import duties/taxes/customs bond (if applicable), any potential customs exams (X-Ray/Vacis).</p> <ul style="list-style-type: none"> <li>- US Customs Entry: US\$225.00 (Includes 3 line items classification)</li> <li>- Additional Classifications if needed: US\$ 15.00 / line item</li> <li>- ISF filing to US Customs: US\$ 35.00</li> <li>- Messenger documents to carrier: US\$ 35.00</li> <li>- Any Destination THC/CUC : At cost if not included</li> </ul> <p><u>The following charges might be applicable:</u></p> <p>Duty: As per customs tariff</p> <p>Harbor Maintenance Fee: 0.125% of declared value</p> <p>Merchandise Processing Fee: 0.3464% of declared value (Min \$25 – Max \$485)</p> <p>Single Transaction Customs Bond: 0.4% of declared value - min \$55.00</p> <p><b>EXCLUDED</b> Security Charges, Import taxes,</p>
---------	---



$$A \times B = \text{sq/mt}$$



Sample of side steel plates

